

Repair Estimate — Hailstorm

Full roof replacement (all slopes), full gutter system replacement, skylight replacement, interior drywall repair under skylight.

ESTIMATE HEADER

Estimate number	LSP-2026-04217	Date prepared	2026-04-25
Prepared for	Maria Chen	Property address	4521 Oak Ridge Dr, Plano TX 75024
Estimator	Brett Halverson, Sr. Estimator	Phone	(972) 555-0188
Software	Xactimate-style	Valid through	2026-05-25

SCOPE NARRATIVE

Property sustained widespread hail impact across all roof slopes during the 04/22/2026 hail event. Recommend full tear-off and replacement of all asphalt composition shingles per manufacturer warranty requirements. Front and rear gutter runs show denting consistent with hail and require replacement to restore matching aluminum profile. Kitchen skylight cracked at glazing — replace unit and reframe as needed. Interior drywall under skylight shows water staining and requires R&R plus paint.

LINE ITEMS (XACTIMATE-STYLE)

CODE	DESCRIPTION	QTY	UNIT	UNIT PRICE	EXTENDED
RFG 240S	Tear off composition shingles — all slopes	32	SQ	\$75.00	\$2,400.00
RFG 240A	Asphalt composition shingles — laminated, all slopes (RCV)	32	SQ	\$280.00	\$8,960.00
RFG UNDR	Synthetic underlayment — full deck	32	SQ	\$32.00	\$1,024.00
RFG IWS	Ice & water shield — eaves & valleys	8	SQ	\$95.00	\$760.00
RFG FLSHG	Drip edge & step flashing — replace all	220	LF	\$4.20	\$924.00
GTR 5KAL	Aluminum gutter — 5" K-style — full system replacement	180	LF	\$11.50	\$2,070.00
GTR DSPT	Aluminum downspouts — 3x4 — replace all	60	LF	\$9.50	\$570.00
SKY 24x48	Skylight — fixed glass 24x48 — R&R unit incl. flashing kit	1	EA	\$1,480.00	\$1,480.00
DRY 1/2	Drywall 1/2" under skylight — R&R, tape & float, prime	96	SF	\$4.20	\$403.20
PNT INT	Interior paint — 2 coats, ceiling, kitchen	96	SF	\$1.80	\$172.80
DBR HAUL	Debris haul-off & disposal	1	EA	\$525.00	\$525.00
OHP O&P	Overhead & profit (10% / 10%)	1	EA	\$551.00	\$551.00

Subtotal (RCV) **\$19,840.00**

Deposit required **\$4,960.00**

Balance on completion **\$14,880.00**

NOTES

Bid is contingent on insurance approval. Lone Star Premier Roofing will work directly with the carrier on supplements. Workmanship warranty: 5 years. Manufacturer warranty: 30 years (limited).

Signed: Brett Halverson
Sr. Estimator

2026-04-25